




Boeing Aerospace Operations

ORBITAL TRANSFER VEHICLE Launch Operations Study

(NASA-CR-179705) ORBITAL TRANSFER VEHICLE
LAUNCH OPERATIONS STUDY: MANPOWER SUMMARY
AND FACILITY REQUIREMENTS, VOLUME 5 Final
Report (Boeing Aerospace Co.) 36 p CSCI 22D

N86-32504

Unclas
G6/14 44599



MANPOWER SUMMARY & FACILITY REQUIREMENTS VOLUME 5 OF 5

MARCH 7, 1986

FINAL REPORT

KENNEDY SPACE CENTER
NAS10-11165

TABLE OF CONTENTS

| | <u>PAGE</u> |
|---|-------------|
| APPENDIX A GBOTV SPREAD SHEET MANPOWER AND TIME SUMMARIES | 5 |
| APENDIX B SBOTV SPREAD SHEET MANPOWER AND TIME SUMMARIES | 11 |
| APPENDIX C FACILITY ANALYSIS | 15 |
| DIGITIZED FACILITY CAPABILITIES | 17 |
| FACILITY REQUIREMENTS GROUND BASED OTV | 25 |
| "BEST FIT" FACILITY IDENTIFICATION REPORT | 29 |
| FACILITY MODIFICATION REPORT | 33 |

THIS PAGE INTENTIONALLY LEFT BLANK

MANPOWER

All manpower numbers: number of heads (by skill), serial time and manhours have been accumulated and compiled on a per subtask basis in spreadsheet format for both the Ground Based and the Space Based flows. These basic data are included as Appendices A and B respectively in this volume so that anyone can run whatever analyses may be of interest or that apply to his/her particular interest or concern.

FACILITY IDENTIFICATION

To aid in identifying the facility resources required to process the GBOTV and/or the SBOTV through the ground facilities at KSC, a software application package was developed using a general purpose Data Base Management System known as Data Flex. The facility requirements, identified on the second page of the Ground Based RIS, are used as the basic input to this software application. The resources of the KSC facilities that could be used by the OTV Program were digitized in the same RIS format used to identify facility requirements. The "facility capabilities" were digitized in this format for subsequent, automated comparative analyses.

The software will accumulate a composite set of facility requirements from any sequential numbered group of the RIS's. The Tasks were grouped into two main task groups, Task Numbers 1 to 13 and Tasks 34 to 39. Composite facility requirement(s) were accumulated for each Task Group.

Composite facility requirements are then compared to each of the Baseline Facility capabilities and the system generates a relative score that indicates how each facility weighs against the composite requirements in relation to the other

facilities in the set. There is no perfect score but a high score is better than a low score. Each requirement can be individually weighted such that a higher priority can be given to selected requirements (such as physical size, crane capacity, or other selection) while maintaining a lower priority for other items like E.C.S, Humidity, or Potable Water. If some items are more critical, expensive, difficult, or whatever; a sort of games-manship can be played by using different weighting factors for the various items, depending upon their relative importance.

Once the system has identified the facility with the Best Fit, those modifications required to make the "Best Fit" facility match the composite requirements are generated. The Modifications report identifies the additions that must be made to the Best Fit Facility. In numeric fields like "Airlock", "High Bay", etc., the number(s) indicated in the report are those deltas in a particular field, in that facility, to bring the field up to the "composite" requirement where the number appears. In non-numeric fields like "Paging", "Vacuums", and "Shop Air", etc., an "N" indicates NO modification is required while a "Y" indicates a modification IS required. No indication is currently provided as to how much, if any, a facility exceeds any of the composite facility requirements.

APPENDIX A

GROUND BASED
ORBITAL TRANSFER VEHICLE
SPREAD SHEET
MANPOWER AND TIME SUMMARIES

| | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 |
|----|------|----------------------------|--------|-----|------|------|-----|--------|--------|--------|-------|-------|
| 1 | | GROUND BASED OTV MANPOWER | | | | | | | | | | |
| 2 | TASK | TITLE | SKILLS | | | | | | TIME | | | |
| 3 | NO. | | | | | | | SERIAL | TOTAL | TOTAL | MAN | TOTAL |
| 4 | | | | | | | | TIME | SERIAL | SERIAL | HOURS | MH |
| 5 | | | P/L | ENG | TECH | QUAL | OTH | (MIN) | TIME | TIME | | |
| 6 | | | SPEC | | | | | | (MIN) | (HRS) | | |
| 7 | | | | | | | | | | | | |
| 8 | 1 | OTV RECEIVING & INSPECTION | | | | | | | | | | |
| 9 | 1.01 | TRANSPORTATION LAND | 0 | 0 | 2 | 1 | 0 | 5760 | | | | |
| 10 | 1.02 | TRANSPORTATION BARGE | 0 | 0 | 2 | 1 | 0 | 5760 | | | 288 | |
| 11 | 1.03 | TRANSPORTATION AIR | 0 | 0 | 1 | 1 | 0 | 480 | | | | |
| 12 | 1.04 | TRANSFER TO RECEIVING | 0 | 2 | 4 | 2 | 0 | 480 | | | 64 | |
| 13 | 1.05 | RECEIVING | 0 | 1 | 2 | 1 | | 480 | | | 32 | |
| 14 | 1.06 | TRNSFR OTV TO OTVPF AIRLK | 0 | 2 | 5 | 1 | 0 | 240 | | | 32 | |
| 15 | 1.07 | TRNSFR OTV TO CLEAN ROOM | 0 | 1 | 5 | 2 | 0 | 480 | | | 64 | |
| 16 | 1.08 | OTV INSPECTION | 0 | 2 | 3 | 1 | 0 | 480 | | | 48 | |
| 17 | 1 | TOTAL | | | | | | | 7920 | 132 | | 528 |
| 18 | 2 | OTV MECHANICAL ASSEMBLY | | | | | | | | | | |
| 19 | 2.01 | INSTALL ASSEMBLY STRUCT | 0 | 2 | 5 | 2 | 0 | 960 | | | 144 | |
| 20 | 2.02 | INSTALL CRYO TANK SET | 0 | 2 | 5 | 2 | 0 | 720 | | | 108 | |
| 21 | 2.03 | INSTALL RCS TANK SET | 0 | 2 | 5 | 2 | 0 | 360 | | | 54 | |
| 22 | 2.04 | INSTL PROPL SYS & CNTRL | 0 | 2 | 5 | 2 | 0 | 480 | | | 72 | |
| 23 | 2.05 | INSTALL RCS/ENGINES | 0 | 2 | 5 | 2 | 0 | 480 | | | 72 | |
| 24 | 2.06 | INSTALL RCS NOZZLE COVERS | 0 | 1 | 3 | 1 | 0 | 60 | | | 5 | |
| 25 | 2.07 | MATE MECH CONNECTIONS | 0 | 1 | 3 | 1 | 0 | 300 | | | 25 | |
| 26 | 2 | TOTAL | | | | | | | 3360 | 56 | | 480 |
| 27 | 3 | ELECTRICAL ASSEMBLY | | | | | | | | | | |
| 28 | 3.01 | INSTALL CABLE HARNESS | 0 | 1 | 3 | 1 | 0 | 360 | | | 30 | |
| 29 | 3.02 | INSTALL POWER SYSTEM | 0 | 1 | 3 | 1 | 0 | 480 | | | 40 | |
| 30 | 3.03 | INSTALL GN&C SYSTEM | 0 | 1 | 3 | 1 | 0 | 240 | | | 20 | |
| 31 | 3.04 | INSTALL AVIONICS SYSTEM | 0 | 1 | 3 | 1 | 0 | 240 | | | 20 | |
| 32 | 3.05 | MAKE ALL ELEC CONNECTORS | 0 | 1 | 3 | 1 | 0 | 300 | | | 25 | |
| 33 | 3 | TOTAL | | | | | | | 1620 | 27 | | 135 |
| 34 | 4 | MECHANICAL SYSTEM TESTS | | | | | | | | | | |
| 35 | 4.01 | LEAK & PRESSURE CHECKS | 0 | 2 | 2 | 2 | 0 | 1380 | | | 138 | |
| 36 | 4 | TOTAL | | | | | | | 1380 | 23 | | 138 |
| 37 | 5 | ELECTRICAL SYSTEMS TEST | | | | | | | | | | |
| 38 | 5.01 | GROUND POWER APPLICATION | 0 | 1 | 2 | 1 | 0 | 240 | | | 16 | |
| 39 | 5.02 | SINGLE POINT GROUND CHECKS | 0 | 1 | 2 | 1 | 0 | 180 | | | 12 | |
| 40 | 5.03 | ACTIVATE POWR/ESSENTL BU | 0 | 3 | 4 | 3 | 0 | 60 | | | 10 | |
| 41 | 5.04 | AVIONICS POWER ON CHECKS | 0 | 3 | 4 | 3 | 0 | 180 | | | 30 | |
| 42 | 5.05 | DPA SUBSYSTEM CHECKS | 0 | 3 | 4 | 3 | 0 | 30 | | | 5 | |
| 43 | 5 | TOTAL | | | | | | | 690 | 11.5 | | 73 |
| 44 | 6 | INTEGRATED SYSTEMS TEST | | | | | | | | | | |
| 45 | 6.01 | AEROBRAKE CONTROL CHECKS | 0 | 4 | 8 | 4 | 0 | 480 | | | 128 | |
| 46 | 6.02 | EXTENDABLE EXIT CONE CHECK | 0 | 4 | 4 | 3 | 0 | 240 | | | 44 | |
| 47 | 6.03 | ENGINE GIMBLE CHECKS | 0 | 4 | 4 | 3 | 0 | 120 | | | 22 | |
| 48 | 6.04 | INTEGRATED SYSTEMS CHECK | 0 | 4 | 4 | 3 | 0 | 1438 | | | 264 | |
| 49 | 6.05 | GPS OPERATION CHECKS | 0 | 4 | 4 | 3 | 0 | 720 | | | 132 | |
| 50 | 6 | TOTAL | | | | | | | 2998 | 50 | | 590 |
| 51 | 7 | OTV/CS-G TEST | | | | | | | | | | |
| 52 | 7.01 | OTVCS RF TEST | 0 | 4 | 4 | 3 | 0 | 960 | | | 176 | |
| 53 | 7 | TOTAL | | | | | | | 960 | 16 | | 176 |

ORIGINAL PAGE IS
OF POOR QUALITY

| | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 |
|-----|-------|----------------------------|---|---|---|---|---|------|------|----|-----|-----|
| 54 | | | | | | | | | | | | |
| 55 | | GROUND BASED OTV MANPOWER | | | | | | | | | | |
| 56 | | PAGE 2 | | | | | | | | | | |
| 57 | | | | | | | | | | | | |
| 58 | 8 | MOVE OTV TO CRYO LOAD FAC | | | | | | | | | | |
| 59 | 8.01 | PREP TRANSPORT TO CRYO FAC | 0 | 1 | 5 | 2 | 0 | 240 | | | 32 | |
| 60 | 8.02 | REMOVE OTV FROM WORKSTAI | 0 | 1 | 5 | 2 | 0 | 540 | | | 72 | |
| 61 | 8.03 | MOVE OTV TO CRYO FACILITY | 0 | 1 | 2 | 1 | 0 | 240 | | | 16 | |
| 62 | 8 | TOTAL | | | | | | | 1020 | 17 | | 120 |
| 63 | 9 | OTV CRYO LOAD & DRAIN | | | | | | | | | | |
| 64 | 9.01 | INSTL OTV INTO CRYO LOAD F | 0 | 1 | 5 | 2 | 0 | 240 | | | 32 | |
| 65 | 9.02 | CONNECT CRYO LINES TO VEH | 0 | 1 | 5 | 2 | 0 | 240 | | | 32 | |
| 66 | 9.03 | LOAD CRYO IN OTV | 0 | 2 | 2 | 2 | 0 | 240 | | | 24 | |
| 67 | 9.04 | VERIFY CRYO LOAD PARA | 0 | 2 | 2 | 2 | 0 | 60 | | | 6 | |
| 68 | 9.05 | LOAD FUEL CELLS | 0 | 2 | 2 | 2 | 0 | 240 | | | 24 | |
| 69 | 9.06 | DRAIN CRYO AND PURGE | 0 | 2 | 2 | 2 | 0 | 240 | | | 24 | |
| 70 | 9.07 | FUEL CELL POWER TEST | 0 | 2 | 2 | 2 | 0 | 240 | | | 24 | |
| 71 | 9.08 | DISCONNECT CRYO LINES | 0 | 1 | 5 | 2 | 0 | 60 | | | 8 | |
| 72 | 9 | TOTAL | | | | | | | 1560 | 26 | | 174 |
| 73 | 10 | MOVE OTV TO SC INTEG FACIL | | | | | | | | | | |
| 74 | 10.01 | REMOVE OTV FROM CRYO STN | 0 | 1 | 5 | 2 | 0 | 120 | | | 16 | |
| 75 | 10.02 | INSTALL OTV INTO TRANSPORT | 0 | 1 | 5 | 2 | 0 | 180 | | | 24 | |
| 76 | 10.03 | MOVE TRANSPORT TO INT FAC | 0 | 1 | 3 | 1 | 0 | 120 | | | 10 | |
| 77 | 10.04 | MOVE TRANSPORT INTO AIRLC | 0 | 1 | 5 | 2 | 0 | 120 | | | 16 | |
| 78 | 10.05 | INSTALL OTV INTO WORKSTAI | 0 | 1 | 5 | 2 | 0 | 240 | | | 32 | |
| 79 | 10 | TOTAL | | | | | | | 780 | 13 | | 98 |
| 80 | 11 | OTV/SC MECH/ELEC MATE | | | | | | | | | | |
| 81 | 11.01 | MECH MATE OTV TO S/C | 0 | 1 | 6 | 2 | 0 | 480 | | | 72 | |
| 82 | 11.02 | ELECT MATE OTV TO S/C | 0 | 1 | 2 | 1 | 0 | 240 | | | 16 | |
| 83 | 11 | TOTAL | | | | | | | 720 | 12 | | 88 |
| 84 | 12 | OTV/SC INTEG TEST | | | | | | | | | | |
| 85 | 12.01 | OTV S/C SINGLE POINT GND | 0 | 1 | 2 | 1 | 0 | 60 | | | 4 | |
| 86 | 12.02 | CONNECT OTV TO GPU | 0 | 1 | 2 | 1 | 0 | 120 | | | 8 | |
| 87 | 12.03 | CONNECT S/C TO GPU | 0 | 1 | 2 | 1 | 0 | 120 | | | 8 | |
| 88 | 12.04 | CONNECT INSTRU CELLS | 0 | 3 | 6 | 4 | 0 | 120 | | | 26 | |
| 89 | 12.05 | CMD/DATA RF CHECKS | 0 | 3 | 4 | 3 | 0 | 300 | | | 50 | |
| 90 | 12.06 | OTV S/C INTERFACE TEST | 0 | 3 | 4 | 3 | 0 | 120 | | | 20 | |
| 91 | 12 | TOTAL | | | | | | | 840 | 14 | | 116 |
| 92 | 13 | OTV/SC/CITE INTERFACE TEST | | | | | | | | | | |
| 93 | 13.1 | DATA PATH VERIFICATION | 0 | 3 | 4 | 3 | 0 | 480 | | | 80 | |
| 94 | 13.2 | FUNCTIONAL VERIF OF RF | 0 | 3 | 4 | 3 | 0 | 1200 | | | 200 | |
| 95 | 13 | TOTAL | | | | | | | 1680 | 28 | | 280 |
| 96 | 14 | CLOSEOUT & PREP TO MOVE | | | | | | | | | | |
| 97 | 14.01 | PREP TO MOVE | 0 | 1 | 5 | 2 | 0 | 720 | | | 96 | |
| 98 | 14 | TOTAL | | | | | | | 720 | 12 | | 96 |
| 99 | 15 | INSTALL IN CANISTER | | | | | | | | | | |
| 100 | 15.01 | INST OTV S/C IN CANISTER | 0 | 1 | 5 | 2 | 0 | 240 | | | 32 | |
| 101 | 15.02 | TRANSPORT CANISTER TO PA | 0 | 1 | 3 | 1 | 0 | 240 | | | 20 | |
| 102 | 15 | TOTAL | | | | | | | 480 | 8 | | 52 |
| 103 | 16 | INSTALL IN RSS PGHM | | | | | | | | | | |
| 104 | 16.01 | MATE CANISTER TO PCR | 0 | 1 | 5 | 2 | 0 | 360 | | | 48 | |
| 105 | 16.02 | REMOVE OTV S/C FRM CANIS | 0 | 1 | 5 | 2 | 0 | 240 | | | 32 | |
| 106 | 16 | TOTAL | | | | | | | 600 | 10 | | 80 |

| | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 |
|-----|-------|-----------------------------|---|---|---|---|---|-----|-----|------|----|-----|
| 107 | | GROUND BASED OTV MANPOWER | | | | | | | | | | |
| 108 | | PAGE 3 | | | | | | | | | | |
| 109 | 17 | ADDN'L SUBSYS INSTALLATION | | | | | | | | | | |
| 110 | 17.01 | CONNECT BATT/ORD TEST SE | 0 | 1 | 4 | 2 | 0 | 60 | | | 7 | |
| 111 | 17.02 | INSTALL BATTERIES | 0 | 1 | 4 | 2 | 0 | 180 | | | 21 | |
| 112 | 17.03 | INSTALL ORDNANCE | 0 | 1 | 4 | 2 | 0 | 360 | | | 42 | |
| 113 | 17.04 | DISCON BATT/ORD TEST SET | 0 | 1 | 4 | 2 | 0 | 120 | | | 14 | |
| 114 | 17.05 | PERFORM PWR TRNSFR CHECK | 0 | 3 | 4 | 3 | 0 | 120 | | | 20 | |
| 115 | 17 | TOTAL | | | | | | | 840 | 14 | | 104 |
| 116 | 18 | LOAD OTV RCS | | | | | | | | | | |
| 117 | 18.01 | CONNECT RCS CART | 0 | 1 | 2 | 1 | 0 | 120 | | | 8 | |
| 118 | 18.02 | FILL RCS TANKS | 0 | 1 | 2 | 1 | 0 | 120 | | | 8 | |
| 119 | 18.03 | DISCONNECT CART | 0 | 1 | 2 | 1 | 0 | 120 | | | 8 | |
| 120 | 18.04 | PREP FOR ORB INSTALLATION | 0 | 1 | 4 | 2 | 0 | 480 | | | 56 | |
| 121 | 18 | TOTAL | | | | | | | 840 | 14 | | 80 |
| 122 | 19 | INSTALL PAYLOAD IN ORBITER | | | | | | | | | | |
| 123 | 19.01 | INSTALL PAYLOAD IN ORBITER | 0 | 1 | 5 | 2 | 0 | 240 | | | 32 | |
| 124 | 19.02 | MATE ELEC/MECH SVC LINES | 0 | 1 | 4 | 2 | 0 | 180 | | | 21 | |
| 125 | 19 | TOTAL | | | | | | | 420 | 7 | | 53 |
| 126 | 20 | P/L TO ORB I/F VERIFICATION | | | | | | | | | | |
| 127 | 20.01 | POWER UP ORBITER | 1 | 0 | 0 | 0 | 0 | 60 | | | 1 | |
| 128 | 20.02 | POWER UP PAYLOAD | 0 | 3 | 4 | 3 | | 180 | | | 30 | |
| 129 | 20.03 | PERFORM CMD TEST VIA MCD | 0 | 3 | 4 | 3 | 0 | 240 | | | 40 | |
| 130 | 20.04 | OTV/SC HEALTH CHECKS | 0 | 3 | 4 | 3 | 0 | 120 | | | 20 | |
| 131 | 20 | TOTAL | | | | | | | 600 | 10 | | 91 |
| 132 | 21 | SPACECRAFT POCC TEST | | | | | | | | | | |
| 133 | 21.01 | ISSUE S/C CMDS FROM POCC | 0 | 3 | 4 | 3 | 0 | 240 | | | 40 | |
| 134 | 21.02 | VERIFY SPACECRAFT RESP | 0 | 3 | 4 | 3 | 0 | 120 | | | 20 | |
| 135 | 21.03 | POWER DOWN SPACECRAFT | 0 | 3 | 4 | 3 | 0 | 60 | | | 10 | |
| 136 | 21 | TOTAL | | | | | | | 420 | 7 | | 70 |
| 137 | 22 | FINAL PAYLOAD CLOSEOUT | | | | | | | | | | |
| 138 | 22.01 | REMOVE BEFORE FLIGHT ITEMS | 0 | 1 | 2 | 1 | 0 | 240 | | | 16 | |
| 139 | 22.02 | APPLY POWER TO SC | 0 | 0 | 0 | 0 | 0 | 240 | | | 0 | |
| 140 | 22.03 | CMD S/C TO PRE-LAUN MODE | 0 | 0 | 0 | 0 | 0 | 30 | | | 0 | |
| 141 | 22.04 | REMOVE POWER FROM SC | 0 | 0 | 0 | 0 | 0 | 60 | | | 0 | |
| 142 | 22.05 | ENGR INSP/FINAL CLOSEOUT | 0 | 2 | 2 | 1 | 0 | 60 | | | 5 | |
| 143 | 22 | TOTAL | | | | | | | 630 | 10.5 | | 21 |
| 144 | 23 | LAUNCH PREPS | | | | | | | | | | |
| 145 | 23.01 | APPLY POWER TO OTV | 0 | 3 | 4 | 3 | 0 | 120 | | | 20 | |
| 146 | 23.02 | LOAD/MONITOR CRYO | 0 | 2 | 2 | 2 | 0 | 120 | | | 12 | |
| 147 | 23.03 | ACTIV/LOAD TEST FUEL CELLS | 0 | 2 | 2 | 2 | 0 | 120 | | | 12 | |
| 148 | 23.04 | LAUNCH | 0 | 2 | 2 | 2 | 0 | 180 | | | 18 | |
| 149 | 23 | TOTAL | | | | | | | 540 | 9 | | 62 |
| 150 | 24 | DEPLOY OTV/SPACECRAFT | | | | | | | | | | |
| 151 | 24.01 | OPEN CARGO BAY DOORS | 1 | 0 | 0 | 0 | 0 | 60 | | | 1 | |
| 152 | 24.02 | POWER UP SPACECRAFT | 1 | 0 | 2 | 2 | 2 | 60 | | | 7 | |
| 153 | 24.03 | PAYLOAD VERIFICATION TEST | 1 | 2 | 2 | 2 | 0 | 240 | | | 28 | |
| 154 | 24.04 | REMOVE P/L FROM CARGO BA | 2 | 2 | 2 | 2 | 0 | 120 | | | 16 | |
| 155 | 24.05 | ELEC/MECH FLUID DISCONNECT | 1 | 2 | 2 | 2 | 0 | 60 | | | 7 | |
| 156 | 24.06 | INSTALL/DEPLOY AEROBRAKE | 3 | 0 | 0 | 0 | 0 | 120 | | | 6 | |
| 157 | 24.07 | PERFORM POCC LAUNCH TEST | 1 | 2 | 2 | 2 | 0 | 60 | | | 7 | |
| 158 | 24.08 | DEPLOY OTV S/C FRM ORBITER | 1 | 2 | 2 | 2 | 0 | 60 | | | 7 | |
| 159 | 24 | TOTAL | | | | | | | 780 | 13 | | 79 |

ORIGINAL PAGE IS
OF POOR QUALITY

| | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 |
|-----|-------|-----------------------------|---|---|---|---|---|-----|------|----|----|-----|
| 160 | | | | | | | | | | | | |
| 161 | | GROUND BASED OTV MANPOWER | | | | | | | | | | |
| 162 | | PAGE 4 | | | | | | | | | | |
| 163 | | | | | | | | | | | | |
| 164 | | | | | | | | | | | | |
| 165 | 25 | LAUNCH FROM LEO | | | | | | | | | | |
| 166 | 25.01 | VERIFY NAV POSITION | 0 | 2 | 2 | 2 | 0 | 60 | | | 6 | |
| 167 | 25.02 | VERIFY PROPULSION SYSTEM | 0 | 2 | 2 | 2 | 0 | 60 | | | 6 | |
| 168 | 25.03 | LAUNCH TO GEO | 0 | 2 | 2 | 2 | 0 | 240 | | | 24 | |
| 169 | 25 | TOTAL | | | | | | | 360 | 6 | | 36 |
| 170 | 26 | PERFORM MISSION | | | | | | | | | | |
| 171 | 26.01 | DEPLOY SPACECRAFT | 0 | 2 | 2 | 2 | 0 | 60 | | | 6 | |
| 172 | 26 | TOTAL | | | | | | | 60 | 1 | | 6 |
| 173 | 27 | ORIENT AND RET - GEO TO LEO | | | | | | | | | | |
| 174 | 27.01 | ISSUE NAV UPDATE | 0 | 2 | 2 | 2 | 0 | 60 | | | 6 | |
| 175 | 27.02 | POSITION OTV TO DE-ORBIT | 0 | 2 | 2 | 2 | 0 | 60 | | | 6 | |
| 176 | 27.03 | FIRE ENGINES | 0 | 2 | 2 | 2 | 0 | 60 | | | 6 | |
| 177 | 27.04 | ORBIT IN LEO | 0 | 2 | 2 | 2 | 0 | 240 | | | 24 | |
| 178 | 27 | TOTAL | | | | | | | 420 | 7 | | 42 |
| 179 | 28 | ORBITER AND OTV RENDEZVOUS | | | | | | | | | | |
| 180 | 28.01 | POS'N OTV IN STANDOFF ORBIT | 0 | 2 | 2 | 2 | 0 | 240 | | | 24 | |
| 181 | 28 | TOTAL | | | | | | | 240 | 4 | | 24 |
| 182 | 29 | OTV RECOVERY | | | | | | | | | | |
| 183 | 29.01 | RETRACT EEC, VERIFY OTV SAI | 0 | 2 | 2 | 2 | 0 | 120 | | | 12 | |
| 184 | 29.02 | VENT OTV CRYO SYSTEM | 2 | 0 | 0 | 0 | 0 | 240 | | | 8 | |
| 185 | 29.03 | OTV CAPTURE | 2 | 0 | 0 | 0 | 0 | 60 | | | 2 | |
| 186 | 29.04 | REM AND STO AEROBRAKE | 3 | 0 | 0 | 0 | 0 | 180 | | | 9 | |
| 187 | 29.05 | LOAD OTV IN ORBITER BAY | 3 | 0 | 0 | 0 | 0 | 120 | | | 6 | |
| 188 | 29.06 | PREPARE OTV FOR DE-ORBIT | 2 | 0 | 0 | 0 | 0 | 180 | | | 6 | |
| 189 | 29 | TOTAL | | | | | | | 900 | 15 | | 43 |
| 190 | 30 | RETURN TO LAUNCH SITE | | | | | | | | | | |
| 191 | 30.01 | DE-ORBIT | 0 | 0 | 0 | 0 | 0 | 0 | | | | |
| 192 | 30.02 | LAND AT KSC | 0 | 0 | 0 | 0 | 0 | 0 | | | | |
| 193 | 30 | TOTAL | | | | | | | 0 | 0 | | 0 |
| 194 | 31 | REMOVE OTV FROM ORBITER | | | | | | | | | | |
| 195 | 31.01 | MOVE ORBITER TO OPF | 0 | 0 | 0 | 0 | 0 | 120 | | | 0 | |
| 196 | 31.02 | REMOVE OTV | 0 | 2 | 4 | 2 | 0 | 180 | | | 24 | |
| 197 | 31.03 | INST OTV IN TRANSPORTER | 0 | 1 | 5 | 2 | 0 | 120 | | | 16 | |
| 198 | 31 | TOTAL | | | | | | | 420 | 7 | | 40 |
| 199 | 32 | | | | | | | | | | | |
| 200 | 32.01 | | | | | | | | | | | |
| 201 | 32 | | | | | | | | 0 | 0 | | 0 |
| 202 | 33 | | | | | | | | | | | |
| 203 | 33.01 | | | | | | | | | | | |
| 204 | 33 | | | | | | | | 0 | 0 | | 0 |
| 205 | 34 | MOVE TO PROCESS FACIL | | | | | | | | | | |
| 206 | 34.01 | MOVE OTV TO OTVPF | 0 | 1 | 3 | 1 | 0 | 120 | | | 10 | |
| 207 | 34.02 | REM OTV FRM TRANSPORTER | 0 | 1 | 5 | 2 | 0 | 300 | | | 40 | |
| 208 | 34.03 | INSTALL OTV IN WORKSTAND | 0 | 1 | 5 | 2 | 0 | 240 | | | 32 | |
| 209 | 34.04 | REMOVE BAT/ORD | 0 | 1 | 4 | 1 | 0 | 180 | | | 18 | |
| 210 | 34.05 | PURGE AND LEAK CHECK CRYO | 0 | 1 | 2 | 1 | 0 | 180 | | | 12 | |
| 211 | 34.06 | INSTALL OTV GPU/GSE | 0 | 1 | 2 | 1 | 0 | 120 | | | 8 | |
| 212 | 34 | TOTAL | | | | | | | 1140 | 19 | | 120 |

| | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 |
|-----|-------|---------------------------|---|---|---|---|---|-----|-------|-----|-----|------|
| 213 | | GROUND BASED OTV MANPOWER | | | | | | | | | | |
| 214 | | PAGE 5 | | | | | | | | | | |
| 215 | 35 | CONDUCT PLANNED MAINT | | | | | | | | | | |
| 216 | 35.01 | REFURB AEROBRAKE SYSTEM | 0 | 2 | 6 | 2 | 0 | 600 | | | 100 | |
| 217 | 35.02 | REM ENG PUMPS FOR REFURB | 0 | 2 | 6 | 2 | 0 | 360 | | | 60 | |
| 218 | 35.03 | REINSTALL ENGINE /PUMPS | 0 | 2 | 6 | 2 | 0 | 360 | | | 60 | |
| 219 | 35.04 | REINSTALL AEROBRAKE ASSY | 0 | 2 | 6 | 2 | 0 | 240 | | | 40 | |
| 220 | 35 | TOTAL | | | | | | | 1560 | 26 | | 260 |
| 221 | 36 | CONDUCT UNPLANNED MAINT | | | | | | | | | | |
| 222 | 36.01 | CONDUCT UNPLANNED MAINT | 0 | 0 | 0 | 0 | 0 | 0 | | | | |
| 223 | 36 | TOTAL | | | | | | | 0 | 0 | | 0 |
| 224 | 37 | INSTALL MODIFICATIONS | | | | | | | | | | |
| 225 | 37.01 | INSTALL MODIFICATIONS | 0 | 0 | 0 | 0 | 0 | 0 | | | | |
| 226 | 37 | TOTAL | | | | | | | 0 | 0 | | 0 |
| 227 | 38 | RETEST VERIFICATION | | | | | | | | | | |
| 228 | 38.01 | APPLY POWER TO OTV | 0 | 3 | 4 | 3 | 0 | 60 | | | 10 | |
| 229 | 38.02 | PERFM OTV HEALTH CHECKS | 0 | 3 | 4 | 3 | 0 | 60 | | | 10 | |
| 230 | 38.03 | REMOVE POWER FROM OTV | 0 | 3 | 4 | 3 | 0 | 60 | | | 10 | |
| 231 | 38 | TOTAL | | | | | | | 180 | 3 | | 30 |
| 232 | 39 | OTV STOR & RTN TO FLOW | | | | | | | | | | |
| 233 | 39.01 | COVER OTV | 0 | 1 | 4 | 2 | 0 | 60 | | | 7 | |
| 234 | 39.02 | SEAL OTV | 0 | 1 | 6 | 2 | 0 | 60 | | | 9 | |
| 235 | 39.03 | REMOVE SEAL | 0 | 1 | 4 | 1 | 0 | 60 | | | 6 | |
| 236 | 39.04 | REMOVE COVERS ON OTV | 0 | 1 | 4 | 1 | 0 | 60 | | | 6 | |
| 237 | 39.05 | RETURN OTV TO FLOW | 0 | 1 | 2 | 1 | 0 | 180 | | | 12 | |
| 238 | 39 | TOTAL | | | | | | | 420 | 7 | | 40 |
| 239 | | | | | | | | | | | | |
| 240 | | GRAND TOTALS FOR GROUND | | | | | | | | | | |
| 241 | | BASED OTV PROCESSING | | | | | | | | | | |
| 242 | | | | | | | | | | | | |
| 243 | | TOTAL SERIAL TIME (MIN) | | | | | | | 38098 | | | |
| 244 | | | | | | | | | | | | |
| 245 | | | | | | | | | | | | |
| 246 | | TOTAL SERIAL TIME (HRS) | | | | | | | | 635 | | |
| 247 | | TOTAL MANHOURS (HRS) | | | | | | | | | | 4425 |
| 248 | | | | | | | | | | | | |
| 249 | | | | | | | | | | | | |
| 250 | | | | | | | | | | | | |
| 251 | | | | | | | | | | | | |
| 252 | | | | | | | | | | | | |
| 253 | | | | | | | | | | | | |
| 254 | | | | | | | | | | | | |
| 255 | | | | | | | | | | | | |

APPENDIX B

SPACE BASED
ORBITAL TRANSFER VEHICLE
SPREAD SHEET
MANPOWER AND TIME SUMMARIES

| | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 |
|----|-------|--------------------------|------|------|------|--------|--------|--------|-----|-------|-------|
| 1 | SPACE | BASED OTV MANPOWER | | | | | | | | | |
| 2 | | REQUIREMENTS | | | | SERIAL | TOTAL | TOTAL | | TOTAL | HOURS |
| 3 | | | STA | STA | CS-G | TIME | SERIAL | SERIAL | IVA | EVA | GND |
| 4 | TASK | TASK TITLE | SPEC | SPEC | | (MIN) | TIME | TIME | | | |
| 5 | NO. | | IVA | EVA | | | (MIN) | (HRS) | | | |
| 6 | | | | | | | | | | | |
| 7 | 1 | RECEIVING & INSPECTION | | | | | | | | | |
| 8 | 1.04 | TRANSFER TO STATION | 1 | 2 | | 240 | | 4 | 4 | 8 | |
| 9 | 1.055 | RECEIVING | 3 | | | 300 | | 5 | 15 | 0 | |
| 10 | 1 | TOTAL | | | | | 540 | 9 | 19 | 8 | |
| 11 | 2 | OTV MECH ASSEMBLY | | | | | | | | | |
| 12 | 2.01 | INSTALL ASSY STRUCTURE | 2 | | | 960 | | 16 | 32 | | |
| 13 | 2.02 | INSTALL CRYO TANK SET | 2 | | | 300 | | 5 | 10 | | |
| 14 | 2.03 | INSTALL RCS TANK SET | 2 | | | 360 | | 6 | 12 | | |
| 15 | 2.04 | INSTL PROPL SYS/CTRL | 2 | | | 480 | | 8 | 16 | | |
| 16 | 2.05 | INSTALL RCS/ENGINES | 2 | | | 480 | | 8 | 16 | | |
| 17 | 2 | TOTAL | | | | | 2580 | 43 | 86 | | |
| 18 | 3 | ELECTRICAL ASSEMBLY | | | | | | | | | |
| 19 | 3.02 | INSTALL POWER SYSTEM | 2 | | | 480 | | 8 | 16 | | |
| 20 | 3.03 | INSTALL GN&C SYSTEM | 2 | | | 240 | | 4 | 8 | | |
| 21 | 3.04 | INSTALL AVIONICS SYSTEM | 2 | | | 240 | | 4 | 8 | | |
| 22 | 3 | TOTAL | | | | | 960 | 16 | 32 | | |
| 23 | 4 | MECHANICAL SYSTEM TEST | | | | | | | | | |
| 24 | 4.01 | LEAK & PRESSURE CHECKS | 2 | | | 1380 | | 23 | 46 | | |
| 25 | 4 | TOTAL | | | | | 1380 | 23 | 46 | | |
| 26 | 5 | ELECTRICAL SYSTEM TEST | | | | | | | | | |
| 27 | 5.015 | SS POWER ACTIVATION | 2 | | | 240 | | 4 | 8 | | |
| 28 | 5.02 | SINGLE POINT GND CKS | 2 | | | 180 | | 3 | 6 | | |
| 29 | 5.03 | ACTIVATE PWR/ESS BUS | 2 | | | 60 | | 1 | 2 | | |
| 30 | 5.04 | AVIONICS POWER ON CKS | 2 | | | 180 | | 3 | 6 | | |
| 31 | 5.05 | DPA SUBSYS CHECKOUT | 2 | | | 30 | | 1 | 1 | | |
| 32 | 5 | TOTAL | | | | | 690 | 12 | 23 | | |
| 33 | 6 | INTEGRATED SYSTEM TEST | | | | | | | | | |
| 34 | 6.01 | AEROBRAKE CONTROL CKS | 2 | | 6 | 240 | | 4 | 8 | | 24 |
| 35 | 6.02 | EXTNDBLE ENGINE CONE CKS | 2 | | 6 | 60 | | 1 | 2 | | 6 |
| 36 | 6.03 | ENGINE GIMBLE CHECKS | 2 | | 6 | 120 | | 2 | 4 | | 12 |
| 37 | 6.04 | INTEGRATED SYS CHECKS | 2 | | 6 | 1440 | | 24 | 48 | | 144 |
| 38 | 6.05 | GPS OPERATION CHECKS | 2 | | 6 | 120 | | 2 | 4 | | 12 |
| 39 | 6 | TOTAL | | | | | 1980 | 33 | 66 | | 198 |
| 40 | 7 | OTV/CS-G TEST | | | | | | | | | |
| 41 | 7.01 | OTVCS RF TEST | 2 | | 6 | 960 | | 16 | 32 | | 96 |
| 42 | 7 | TOTAL | | | | | 960 | 16 | 32 | | 96 |
| 43 | 11 | OTV SPACECRAFT MATE | | | | | | | | | |
| 44 | 11.01 | MECH MATE OTV TO SC | 1 | 2 | 6 | 360 | | 6 | 6 | 12 | 36 |
| 45 | 11.02 | ELEC MATE OTV TO SC | 1 | 2 | 6 | 240 | | 4 | 4 | 8 | 24 |
| 46 | 11 | TOTAL | | | | | 600 | 10 | 10 | 20 | 60 |
| 47 | 12 | OTV SC INTEGRATION | | | | | | | | | |
| 48 | 12.05 | CMD/DATA RF CHECKS | 2 | | 6 | 300 | | 5 | 10 | | 30 |
| 49 | 12.06 | OTV SC INTERFACE TEST | 2 | | 6 | 120 | | 2 | 4 | | 12 |
| 50 | 0 | TOTAL | | | | | 420 | 7 | 14 | | 42 |
| 51 | | | | | | | | | | | |
| 52 | | | | | | | | | | | |
| 53 | | | | | | | | | | | |

| | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 |
|-----|--------|-------------------------|---|---|---|-----|------|----|----|----|-----|
| 54 | SPACE | BASED OTV MANPOWER | | | | | | | | | |
| 55 | | REQUIREMENTS | | | | | | | | | |
| 56 | | PAGE 2 | | | | | | | | | |
| 57 | 17 | INSTALL BATT & ORD | 2 | | 6 | 180 | | 3 | 6 | | 18 |
| 58 | 17.02 | INSTALL BATTERIES | 2 | | 6 | 360 | | 6 | 12 | | 36 |
| 59 | 17.03 | INSTALL ORDNANCE | 2 | | 6 | 120 | | 2 | 4 | | 12 |
| 60 | 17.05 | PERFORM PWR XFER CKS | | | | | 660 | 11 | 22 | | 66 |
| 61 | 17 | TOTAL | | | | | | | | | |
| 62 | 18 | LOAD OTV RCS | 2 | | 6 | 120 | | 2 | 4 | | 12 |
| 63 | 18.02 | FILL RCS TANKS | | | | | 120 | 2 | 4 | | 12 |
| 64 | 18 | TOTAL | | | | | | | | | |
| 65 | 21 | SPACECRAFT POCC TEST | 2 | | 6 | 240 | | 4 | 8 | | 24 |
| 66 | 21.01 | ISSUE SC CMDS - POCC | 2 | | 6 | 120 | | 2 | 4 | | 12 |
| 67 | 21.02 | VERIFY SC RESPONSE | 2 | | 6 | 60 | | 1 | 2 | | 6 |
| 68 | 21.03 | POWER DN SPACECRAFT | | | | | 420 | 7 | 14 | | 42 |
| 69 | 21 | TOTAL | | | | | | | | | |
| 70 | 22 | CLOSEOUT/ PREPS TO MOVE | 2 | | 6 | 720 | | 12 | 24 | | 72 |
| 71 | 22.015 | DISCONNECT UMBILICALS | 2 | | 6 | 240 | | 4 | 8 | | 24 |
| 72 | 22.025 | MOVE FROM HANGAR | 2 | | 6 | 120 | | 2 | 4 | | 12 |
| 73 | 22.035 | INSTALL/DEPLOY BRAKE | 2 | | 6 | 240 | | 4 | 8 | | 24 |
| 74 | 22.045 | INSTALL OMV ON THE OTV | 2 | | 6 | 240 | | 4 | 8 | | 24 |
| 75 | 22.055 | PL/OMV TO LAUNCH SITE | | | | | 1560 | 26 | 52 | | 156 |
| 76 | 22 | TOTAL | | | | | | | | | |
| 77 | 23 | OTV/SC LAUNCH PREPS | 2 | | 6 | 60 | | 1 | 2 | | 6 |
| 78 | 23.01 | APPLY POWER TO OTV | 2 | | 6 | 480 | | 8 | 16 | | 48 |
| 79 | 23.02 | LOAD/MONITOR CRYO | 2 | | 6 | 120 | | 2 | 4 | | 12 |
| 80 | 23.03 | ACTIV/LOAD FUEL CELLS | 2 | | 6 | 240 | | 4 | 8 | | 24 |
| 81 | 23.045 | APPLY PWR TO SC | 2 | | 6 | 30 | | 1 | 1 | | 3 |
| 82 | 23.055 | SC TO PRELAUN MODE | | | | | 930 | 16 | 31 | | 93 |
| 83 | 23 | TOTAL | | | | | | | | | |
| 84 | 24 | DEPLOY OTV/SC | 2 | | 6 | 60 | | 1 | 2 | | 6 |
| 85 | 24.07 | PERFM POCC TESTS | 2 | | 6 | 300 | | 5 | 10 | | 30 |
| 86 | 24.085 | REL OTV/SC FRM OMV | | | | | 360 | 6 | 12 | | 36 |
| 87 | 24 | TOTAL | | | | | | | | | |
| 88 | 25 | LAUNCH FROM LEO | 2 | | 6 | 60 | | 1 | 2 | | 6 |
| 89 | 25.01 | VERIFY NAV POSITION | 2 | | 6 | 60 | | 1 | 2 | | 6 |
| 90 | 25.02 | VERIFY PROPUL SYSTEM | 2 | | 6 | 240 | | 4 | 8 | | 24 |
| 91 | 25.03 | LAUNCH TO GEO | | | | | 360 | 6 | 12 | | 36 |
| 92 | 25 | TOTAL | | | | | | | | | |
| 93 | 26 | PERFORM MISSION | 2 | | 6 | 60 | | 1 | 2 | | 6 |
| 94 | 26.01 | DEPLOY SPACECRAFT | | | | | 60 | 1 | 2 | | 6 |
| 95 | 26 | TOTAL | | | | | | | | | |
| 96 | 27 | ORIENT/RTN - GEO TO LEO | 2 | | 6 | 60 | | 1 | 2 | | 6 |
| 97 | 27.01 | ISSUE NAV UPDATE | 2 | | 6 | 60 | | 1 | 2 | | 6 |
| 98 | 27.02 | ORIENT OTV TO DE-ORBIT | 2 | | 6 | 60 | | 1 | 2 | | 6 |
| 99 | 27.03 | FIRE ENGINES | 2 | | 6 | 240 | | 4 | 8 | | 24 |
| 100 | 27.04 | ORBIT IN LEO | | | | | 420 | 7 | 14 | | 42 |
| 101 | 27 | TOTAL | | | | | | | | | |
| 102 | 28 | S.S. / OTV RENDEZVOUS | 2 | | 6 | 240 | | 4 | 8 | | 24 |
| 103 | 28.01 | POS OTV-ST ANDOFF ORBIT | | | | | 240 | 4 | 8 | | 24 |
| 104 | 28 | TOTAL | | | | | | | | | |
| 105 | | | | | | | | | | | |
| 106 | | | | | | | | | | | |

| | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 |
|-----|--------|--------------------------|---|---|---|-----|------|----|----|----|----|
| 107 | SPACE | BASED OTV MANPOWER | | | | | | | | | |
| 108 | | REQUIREMENTS | | | | | | | | | |
| 109 | | PAGE 3 | | | | | | | | | |
| 110 | 29 | OTV RECOVERY | 2 | | 6 | 120 | | 2 | 4 | | 12 |
| 111 | 29.01 | RETRACT EEC, VERIF SAFE | 2 | | 6 | 240 | | 4 | 8 | | 24 |
| 112 | 29.02 | VENT OTV CRYO SYSTEM | 2 | | 6 | 60 | | 1 | 2 | | 6 |
| 113 | 29.03 | OTV CAPTURE | | | | | 420 | 7 | 14 | | 42 |
| 114 | 29 | TOTAL | | | | | | | | | |
| 115 | 34 | MOVE TO PROCESSING FAC | 2 | | | 300 | | 5 | 10 | | |
| 116 | 34.015 | USE MRMS, OTV INTO HGR | 1 | 2 | | 720 | | 12 | 12 | 24 | |
| 117 | 34.025 | REMOVE AND STORE BRAKE | 2 | | | 240 | | 4 | 8 | | |
| 118 | 34.03 | INSTL OTV IN WORKSTAND | 2 | | | 180 | | 3 | 6 | | |
| 119 | 34.04 | REMOVE BAT/ORD | 2 | | | 300 | | 5 | 10 | | |
| 120 | 34.055 | CONNECT UMBILICALS | | | | | 1740 | 29 | 46 | 24 | |
| 121 | 34 | TOTAL | | | | | | | | | |
| 122 | 35 | CONDUCT PLANNED MAINT | 2 | | | 600 | | 10 | 20 | | |
| 123 | 35.01 | REFURBISH AEROBRAKE SYS | 2 | | | 360 | | 6 | 12 | | |
| 124 | 35.02 | REMOVE PUMPS & STORE | 2 | | | 360 | | 6 | 12 | | |
| 125 | 35.03 | REINSTL ENGINES/PUMPS | | | | | 1320 | 22 | 44 | | |
| 126 | 35 | TOTAL | | | | | | | | | |
| 127 | 36 | CONDUCT UNPLAN MAINT | | | | 0 | | | | | |
| 128 | 36.01 | CONDUCT UNPLAN MAINT | | | | | 0 | 0 | 0 | 0 | 0 |
| 129 | 36 | TOTAL | | | | | | | | | |
| 130 | 37 | INSTALL MODIFICATIONS | | | | 0 | | | | | |
| 131 | 37.01 | INSTALL MODIFICATIONS | | | | | 0 | 0 | 0 | 0 | 0 |
| 132 | 37 | TOTAL | | | | | | | | | |
| 133 | 38 | RETEST VERIFICATION | 2 | | 6 | 60 | | 1 | 2 | | 6 |
| 134 | 38.01 | APPLY POWER TO OTV | 2 | | 6 | 60 | | 1 | 2 | | 6 |
| 135 | 38.02 | PERFM OTV HEALTH CKS | 2 | | 6 | 60 | | 1 | 2 | | 6 |
| 136 | 38.03 | POWER DN OTV | | | | | 180 | 3 | 6 | | 18 |
| 137 | 38 | TOTAL | | | | | | | | | |
| 138 | 39 | OTV STO/RET TO FLOW | 1 | 2 | | 60 | | 1 | 1 | 2 | 0 |
| 139 | 39.01 | COVER OTV | 1 | 2 | | 60 | | 1 | 1 | 2 | |
| 140 | 39.02 | SEAL OTV | 1 | 2 | | 60 | | 1 | 1 | 2 | |
| 141 | 39.03 | REMOVE SEAL | 1 | 2 | | 60 | | 1 | 1 | 2 | |
| 142 | 39.04 | REMOVE COV & RET TO FLOW | | | | | 240 | 4 | 4 | 8 | 0 |
| 143 | 39 | TOTAL | | | | | | | | | |
| 144 | | | | | | | | | | | |
| 145 | | TOTAL FLOW TIME | | | | | | | | | |
| 146 | | SERIAL TIME (MINUTES) | | | | | | | | | |
| 147 | | 19140 | | | | | | | | | |
| 148 | | | | | | | | | | | |
| 149 | | SERIAL TIME (HOURS) | | | | | | | | | |
| 150 | | 319 | | | | | | | | | |
| 151 | | | | | | | | | | | |
| 152 | | IVA TIME (HOURS) | | | | | | | | | |
| 153 | | 613 | | | | | | | | | |
| 154 | | | | | | | | | | | |
| 155 | | EVA TIME (HOURS) | | | | | | | | | |
| 156 | | 60 | | | | | | | | | |
| 157 | | | | | | | | | | | |
| 158 | | CS-G TIME (HOURS) | | | | | | | | | |
| 159 | | 969 | | | | | | | | | |

APPENDIX C

FACILITY ANALYSIS

THIS PAGE INTENTIONALLY LEFT BLANK

DIGITIZED FACILITY CAPABILITIES

PRECEDING PAGE BLANK NOT FILMED

DETAILED <VERT PROCESSING FAC > FACILITY RESOURCES

| | | | |
|----------------|------------------------|-----------------|-------------------|
| Physical Size: | | Crane Capacity: | |
| Air Lock: | 42 74 74 [W/D/H][ft] | 10 Ton | 69 Ft.Hook Height |
| Doors: | 26 72 [W/H][ft] | | |
| High Bay: | 71 143 105 [W/D/H][ft] | 25 Ton | 95 Ft.Hook Height |

| | | |
|------------------------------|--|--------------------|
| Standard Commerical Power: Y | Instrumentation Power [Uninterrupted]: Y | |
| Cleanliness: 100K | E.C.S: Humidity: | Temperature: |
| | 45 +/- 5 % | 75 +/- 3 F |
| Closed Circuit Television: Y | Power Cutoff: Y | Facility GN2: Y |
| Fuel/Oxidizer Disposal: Y | Helium Supply: Y | Shop Air: Y |
| Fire Protection/Deluge: C | Shower/Eye Wash: Y | Vacuum: Y |
| Lightning Protection: Y | Potable Water: Y | Paging: Y |
| Commerical Telephone: Y | RF System: C | OIS: Y |
| Personnel Airlock: Y | Grounding: Y | Explosion Proof: N |

DETAILED <SAEF 2

> FACILITY RESOURCES

Physical Size:

Air Lock: 41 58 52 [W/D/H][ft]
 Doors: 21 39 [W/H][ft]
 High Bay: 49 99 74 [W/D/H][ft]

Crane Capacity:

10 Ton 45 Ft. Hook Height
 10 Ton 65 Ft. Hook Height

Standard Commerical Power: Y

Instrumentation Power [Uninterrupted]: N

Cleanliness: 100K

E.C.S: Humidity:
 45 +/- 5 %

Temperature:
 75 +/- 3 F

Closed Circuit Television: Y

Power Cutoff: Y

Facility GN2: Y

Fuel/Oxidizer Disposal: Y

Helium Supply: N

Shop Air: Y

Fire Protection/Deluge: A

Shower/Eye Wash: Y

Vacuum: Y

Lightning Protection: Y

Potable Water: Y

Paging: Y

Commerical Telephone: Y

RF System: A

OIS: Y

Personnel Airlock: Y

Grounding: Y

Explosion Proof: Y

DETAILED <HANGAR S

> FACILITY RESOURCES

Physical Size:

Air Lock: 14 20 19 [W/D/H][ft]
 Doors: 16 20 [W/H][ft]
 High Bay: 45 55 17 [W/D/H][ft]

Crane Capacity:

2 Ton 19 Ft.Hook Height
 5 Ton 20 Ft.Hook Height

Standard Commerical Power: Y

Instrumentation Power [Uninterrupted]: Y

Cleanliness: 100K

E.C.S: Humidity:
 50 +/- 5 %

Temperature:
 76 +/- 3 F

Closed Circuit Television: N

Power Cutoff: Y

Facility GN2: Y

Fuel/Oxidizer Disposal: N

Helium Supply: Y

Shop Air: Y

Fire Protection/Deluge: A

Shower/Eye Wash: Y

Vacuum: Y

Lightning Protection: Y

Potable Water: Y

Paging: Y

Commerical Telephone: Y

RF System: C

OIS: Y

Personnel Airlock: Y

Grounding: Y

Explosion Proof: N

DETAILED <HANGAR AO

> FACILITY RESOURCES

Physical Size:

Air Lock: 25 29 50 [W/D/H][ft]
 Doors: 24 39 [W/H][ft]
 High Bay: 45 175 50 [W/D/H][ft]

Crane Capacity:

10 Ton 47 Ft.Hook Height
 10 Ton 48 Ft.Hook Height

Standard Commerical Power: Y

Instrumentation Power [Uninterrupted]: Y

Cleanliness: 100K

E.C.S: Humidity:
 50 +/- 5 %

Temperature:
 75 +/- 3 F

Closed Circuit Television: Y

Power Cutoff: Y

Facility GN2: N

Fuel/Oxidizer Disposal: N

Helium Supply: N

Shop Air: Y

Fire Protection/Deluge: A

Shower/Eye Wash: N

Vacuum: Y

Lightning Protection: Y

Potable Water: Y

Paging: Y

Commerical Telephone: Y

RF System: C

OIS: Y

Personnel Airlock: Y

Grounding: Y

Explosion Proof: N

DETAILED <HANGAR AM

> FACILITY RESOURCES

Physical Size:

Air Lock: 0 0 0 [W/D/H][ft]
 Doors: 15 34 [W/H][ft]
 High Bay: 63 70 35 [W/D/H][ft]

Crane Capacity:

0 Ton 0 Ft.Hook Height
 5 Ton 36 Ft.Hook Height

Standard Commerical Power: Y

Instrumentation Power [Uninterrupted]: Y

Cleanliness: 100K

E.C.S: Humidity:
 45 +/- 5 %

Temperature:
 75 +/- 5 F

Closed Circuit Television: Y

Power Cutoff: Y

Facility GN2: N

Fuel/Oxidizer Disposal: N

Helium Supply: N

Shop Air: Y

Fire Protection/Deluge: N

Shower/Eye Wash: N

Vacuum: N

Lightning Protection: Y

Potable Water: Y

Paging: Y

Commerical Telephone: Y

RF System: C

OIS: Y

Personnel Airlock: N

Grounding: Y

Explosion Proof: N

DETAILED <HANGAR AE

> FACILITY RESOURCES

Physical Size:

Air Lock: 25 40 17 [W/D/H][ft]
 Doors: 14 36 [W/H][ft]
 High Bay: 43 51 34 [W/D/H][ft]

Crane Capacity:

2 Ton 20 Ft.Hook Height
 6 Ton 38 Ft.Hook Height

Standard Commerical Power: Y

Instrumentation Power [Uninterrupted]: Y

Cleanliness: 10K

E.C.S: Humidity:
 55 +/- 5 %

Temperature:
 72 +/- 3 F

Closed Circuit Television: Y

Power Cutoff: Y

Facility GN2: Y

Fuel/Oxidizer Disposal: N

Helium Supply: N

Shop Air: Y

Fire Protection/Deluge: A

Shower/Eye Wash: N

Vacuum: Y

Lightning Protection: Y

Potable Water: Y

Paging: Y

Commerical Telephone: Y

RF System: C

OIS: Y

Personnel Airlock: Y

Grounding: Y

Explosion Proof: N

DETAILED <CARGO HAZ SERV FACIL> FACILITY RESOURCES

| | | | | | |
|------------------------------|----|-----|--|--------------------|-------------------|
| Physical Size: | | | Crane Capacity: | | |
| Air Lock: | 54 | 80 | 81 [W/D/H][ft] | 15 Ton | 75 Ft.Hook Height |
| Doors: | 35 | 75 | [W/H][ft] | | |
| High Bay: | 65 | 152 | 94 [W/D/H][ft] | 50 Ton | 85 Ft.Hook Height |
| Standard Commerical Power: Y | | | Instrumentation Power [Uninterrupted]: Y | | |
| Cleanliness: 100K | | | E.C.S: Humidity: | Temperature: | |
| | | | 50 +/- 5 % | 75 +/- 5 F | |
| Closed Circuit Television: Y | | | Power Cutoff: Y | Facility GN2: Y | |
| Fuel/Oxidizer Disposal: Y | | | Helium Supply: Y | Shop Air: Y | |
| Fire Protection/Deluge: C | | | Shower/Eye Wash: Y | Vacuum: Y | |
| Lightning Protection: Y | | | Potable Water: Y | Paging: Y | |
| Commerical Telephone: Y | | | RF System: A | OIS: Y | |
| Personnel Airlock: Y | | | Grounding: Y | Explosion Proof: N | |

FACILITY REQUIREMENTS

GROUND BASED OTV

The best fit KSC facility for tasks No. 1 to 13 is the CARGO HAZ SERV FACIL:

The following additions to the CARGO HAZ SERV FACIL are required to exactly fit those requirements as defined in tasks No. 1 to 13:

| | | | | | |
|------------------------------|----|---|--|----------------------|------------------|
| Physical Size: | | | Crane Capacity: | | |
| Air Lock: | 0 | 0 | 0 [W/D/H][ft] | 0 Ton | 0 Ft.Hook Height |
| Doors: | 0 | 0 | [W/H][ft] | | |
| High Bay: | 5 | 0 | 0 [W/D/H][ft] | 0 Ton | 0 Ft.Hook Height |
| Standard Commerical Power: N | | | Instrumentation Power [Uninterrupted]: N | | |
| Cleanliness: | OK | | E.C.S: Humidity: | Temperature: | |
| | | | 0 +/- 0 % | 0 +/- 5 F | |
| Closed Circuit Television: | N | | Power Cutoff: | N Facility GN2: N | |
| Fuel/Oxidizer Disposal: | N | | Helium Supply: | N Shop Air: N | |
| Fire Protection/Deluge: | N | | Shower/Eye Wash: | N Vacuum: N | |
| Lightning Protection: | N | | Potable Water: | N Paging: N | |
| Commerical Telephone: | N | | RF System: | C OIS: N | |
| Personnel Airlock: | N | | Grounding: | N Explosion Proof: Y | |

Legend:

The NUMBERS indicated in this report are those POSITIVE deltas to be supplied to meet the requirements.

"N"= NO modification is required in the CARGO HAZ SERV FACIL facility:

"Y"= A modification IS required in the CARGO HAZ SERV FACIL facility:

| | |
|--|-------------------------------|
| Fire Protection/Deluge= A: fire protection | RF System= A: S Band & C Band |
| or B: deluge | or B: Ku Band |
| or C: both | or C: both |
| or N: none | or N: none |

Detailed Composite Facility Resources For Task No. 34 to 39

| | | | | | |
|------------------------------|-----------|-------------|--|----------------------|--|
| Physical Size: | | | Crane Capacity: | | |
| Air Lock: | 40 40 50 | [W/D/H][ft] | 10 Ton | 45 Ft.Hook Height | |
| Doors: | 35 45 | [W/H][ft] | | | |
| High Bay: | 70 100 85 | [W/D/H][ft] | 20 Ton | 20 Ft.Hook Height | |
| Standard Commerical Power: Y | | | Instrumentation Power [Uninterrupted]: Y | | |
| Cleanliness: | 100K | | E.C.S: Humidity: | Temperature: | |
| | | | 50 +/- 5 % | 70 +/- 5 F | |
| Closed Circuit Television: | Y | | Power Cutoff: | Y Facility GN2: Y | |
| Fuel/Oxidizer Disposal: | Y | | Helium Supply: | Y Shop Air: Y | |
| Fire Protection/Deluge: | C | | Shower/Eye Wash: | Y Vacuum: NA | |
| Lightning Protection: | Y | | Potable Water: | Y Paging: Y | |
| Commerical Telephone: | Y | | RF System: | A OIS: Y | |
| Personnel Airlock: | Y | | Grounding: | Y Explosion Proof: Y | |

THIS PAGE INTENTIONALLY LEFT BLANK

"BEST FIT"
REPORT

PRECEDING PAGE BLANK NOT FILMED

Generating Facility Matches for Ground Based OTV Operations
For Task No: 1 to 13

The following facilities are being evaluated:

| No. | Facility | Score |
|-----|----------------------|-------|
| 1 | CARGO HAZ SERV FACIL | 58 |
| 2 | HANGAR AM | 21 |
| 3 | HANGAR AO | 36 |
| 4 | HANGAR S | 26 |
| 5 | HANGAR AE | 28 |
| 6 | SAEF 2 | 42 |
| 7 | VERT PROCESSING FAC | 58 |

Generating Facility Matches for Ground Based OTV Operations
For Task No: 34 to 39

The following facilities are being evaluated:

| No. | Facility | Score |
|-----|----------------------|-------|
| 1 | CARGO HAZ SERV FACIL | 58 |
| 2 | HANGAR AM | 20 |
| 3 | HANGAR AO | 34 |
| 4 | HANGAR S | 24 |
| 5 | HANGAR AE | 26 |
| 6 | SAEF 2 | 42 |
| 7 | VERT PROCESSING FAC | 56 |

THIS PAGE INTENTIONALLY LEFT BLANK

FACILITY MODIFICATION REPORT

PRECEDING PAGE BLANK NOT FILMED

Detailed Composite Facility Resources For Task No. 1 to 13

| | | | | | |
|------------------------------|-----------|-------------|--|----------------------|-------------|
| Physical Size: | | | Crane Capacity: | | |
| Air Lock: | 40 40 50 | [W/D/H][ft] | 10 Ton | 45 Ft. | Hook Height |
| Doors: | 35 45 | [W/H][ft] | | | |
| High Bay: | 70 100 85 | [W/D/H][ft] | 20 Ton | 20 Ft. | Hook Height |
| Standard Commerical Power: Y | | | Instrumentation Power [Uninterrupted]: Y | | |
| Cleanliness: | 100K | | E.C.S: Humidity: | Temperature: | |
| | | | 50 +/- 5 % | 70 +/- 5 F | |
| Closed Circuit Television: | Y | | Power Cutoff: | Y Facility GN2: Y | |
| Fuel/Oxidizer Disposal: | Y | | Helium Supply: | Y Shop Air: Y | |
| Fire Protection/Deluge: | C | | Shower/Eye Wash: | Y Vacuum: Y | |
| Lightning Protection: | Y | | Potable Water: | Y Paging: Y | |
| Commerical Telephone: | Y | | RF System: | C OIS: Y | |
| Personnel Airlock: | Y | | Grounding: | Y Explosion Proof: Y | |

The best fit KSC facility for tasks No. 34 to 39 is the CARGO HAZ SERV FACIL:

The following additions to the CARGO HAZ SERV FACIL are required to exactly fit those requirements as defined in tasks No. 34 to 39:

| | | | | | |
|------------------------------|----|---|--|----------------------|------------------|
| Physical Size: | | | Crane Capacity: | | |
| Air Lock: | 0 | 0 | 0 [W/D/H][ft] | 0 Ton | 0 Ft.Hook Height |
| Doors: | 0 | 0 | [W/H][ft] | | |
| High Bay: | 5 | 0 | 0 [W/D/H][ft] | 0 Ton | 0 Ft.Hook Height |
| Standard Commerical Power: N | | | Instrumentation Power [Uninterrupted]: N | | |
| Cleanliness: | OK | | E.C.S: Humidity: | Temperature: | |
| | | | 0 +/- 0 % | 0 +/- 5 F | |
| Closed Circuit Television: | N | | Power Cutoff: | N Facility GN2: N | |
| Fuel/Oxidizer Disposal: | N | | Helium Supply: | N Shop Air: N | |
| Fire Protection/Deluge: | N | | Shower/Eye Wash: | N Vacuum: NA | |
| Lightning Protection: | N | | Potable Water: | N Paging: N | |
| Commerical Telephone: | N | | RF System: | N OIS: N | |
| Personnel Airlock: | N | | Grounding: | N Explosion Proof: Y | |

Legend:

The NUMBERS indicated in this report are those POSITIVE deltas to be supplied to meet the requirements.

"N"= NO modification is required in the CARGO HAZ SERV FACIL facility:

"Y"= A modification IS required in the CARGO HAZ SERV FACIL facility:

| | |
|--|-------------------------------|
| Fire Protection/Deluge= A: fire protection | RF System= A: S Band & C Band |
| or B: deluge | or B: Ku Band |
| or C: both | or C: both |
| or N: none | or N: none |